

**TOWN OF RIDGWAY**

**STANDARD SPECIFICATION AND**

**TYPICAL DRAWINGS**

**FOR INFRASTRUCTURE CONSTRUCTION**

**APRIL, 2001**

These standards, drawings, and supporting reports, plans, files, field data, notes, and other documents and instruments prepared by Consolidated Consulting Services (CCS) as instruments of service shall remain the property of CCS and the Town of Ridgway. The Town and CCS shall retain all common law, statutory, and other reserved rights, including the copyright thereto. These documents may not be used by others or duplicated for any other purpose.

TABLE OF CONTENTS

CHAPTER 1 - GENERAL REOUTREMENTS

0. GENERAL PROVISIONS
1. PURPOSE
2. APPLICABILITY
3. INTERPRETATION
4. AMENDMENTS AND REVISIONS
5. DEFINITIONS AND ABBREVIATIONS
6. ENFORCEMENT
  - 6.01 Authority of Town
  - 6.02 Violations
  - 6.03 Deviations
7. RESPONSIBLE PARTY RESPONSIBILITIES
8. PLANS FOR REVIEW
9. EASEMENT REQUIREMENTS
10. SUBMITTALS
11. RESPONSIBILITY FOR DESIGN AND CONSTRUCTION
12. PRE-CONSTRUCTION MBEETINGS
  - 12.01 Pre-bid Meeting
  - 12.02 Pre-construction Meeting
13. NOTIFICATIONS BY RESPONSIBLE PARTY
14. CONTROL OF WORK AND MATERIALS
  - 14.01 Work Hours
  - 14.02 Authority of Town
  - 14.03 Responsibility of Responsible Party
  - 14.04 Delivery and Storage of Materials
  - 14.05 Work Conditions
  - 14.06 Defective Materials
  - 14.07 Unacceptable or Authorized Work
15. PROTECTION OF FACILITIES, PROPERTY, AND IMPROVEMENTS
  - 15.01 Protection of Existing Facilities and Improvements
  - 15.02 Utility Relocation
  - 15.03 Responsibility for Repair
  - 15.04 Public Safety and Convenience
  - 15.05 Protection of Water Supply, Lakes, Streams, and Reservoirs
16. SAFETY
17. SANITATION FACILITIES
18. TRAFFIC CONTROL
19. STOP WORK ORDER
20. PRECEDENCE OF SPECIFICATIONS AND TYPICAL DRAWINGS
21. CHANGES TO APPROVED PLANS AND SPECIFICATIONS
22. RECORD DRAWINGS AND OPERATION AND MAINTENANCE DATA
23. ACCEPTANCE, OPERATION AND MAINTENANCE
24. SERVICE RATES

TRENCH EXCAVATION AND BACKFILL

PART I - GENERAL

Existing Conditions

Protection of Existing Utilities

PART II - PRODUCTS

Bedding Materials  
Unsuitable Materials

PART III - EXECUTION

Clearing and Grubbing  
    Removal of Cleared and Unsuitable Materials  
Access Roads and Bypasses  
Pavement Cutting  
Excavation  
    Grade Stakes  
    Stockpiling Materials  
    Sheeting, Bracing, and Shoring  
    Drainage and Groundwater Control  
    Use of Explosives  
    Sequencing  
    Excavation to Grade  
    Trench Width  
Pipe Bedding  
    Bedding Classes  
    Bedding Preparation  
    Placing Bedding Material  
Backfill and Compaction  
    Pipe Zone Compaction  
    Upper Trench Compaction  
    Typical Methodology  
    Compaction Around Appurtenances  
    Testing  
        Soil Compaction Tests  
        Density Control  
Surface Restoration  
Bedding Details

WATER DISTRIBUTION SYSTEM - MINIMUM DESIGN STANDARDS

MATERIALS

Plastic Pipe  
Gate Valves  
Fire Hydrants

MINIMUM FLOW

LINE SIZE

WATER LINE LOOPING

VALVE SPACING

HYDRANTS

CROSS CONNECTIONS

SERVICE CONNECTIONS

PROXIMITY STATEMENT

TESTING

## WATER LINE CONSTRUCTION

### PART I - GENERAL

Description  
Related Work Specified Elsewhere  
Proximity Statement

### PART II - PRODUCTS

Ductile Iron Pipe  
Plastic Pipe  
Gate Valves  
Fire Hydrants  
Air Valves  
Cross Connection Control Valves  
Miscellaneous Valves

### PART III - EXECUTION

Field Locations  
Service Disruption  
Receiving, Handling, and Storage  
Alignment and Grade  
Excavation and Trench Preparation  
Pipe Laying  
    Lowering Pipe into trench  
    Inspection before installation  
    Keeping pipe clean  
    Laying of pipe  
    Sequencing  
    Cutting of Pipe  
    Connection to and Crossing Existing Lines  
    Crossings  
    Setting of Fittings, Valves, and Hydrants  
    Dead ends  
    Thrust Blocks  
    Valves and Valve Boxes  
    Hydrants  
    Air Valves  
    Cross Connection Control Valves  
    Vaults  
    Concrete encasements  
Bedding and Compaction  
Hydrostatic Testing  
Disinfection of Potable Water Lines  
    General  
    Pipe Cleaning  
    Preliminary Flushing  
    Chlorine Application  
    Continuous Feed Method  
    Tablet Method  
    Disinfecting Existing Mains  
    Swabbing with Hypochlorite Solution

Flushing  
Final Flushing  
Bacteriological Tests  
Repetition of Procedure

WATER SERVICE CONNECTIONS

PART I - GENERAL

Work Included  
Related Work Specified Elsewhere

PART II - PRODUCTS

PART III - EXECUTION

General  
Depth of Bury  
Meter Lid Elevation  
Installation

SEWER SYSTEM - MINIMUM DESIGN STANDARDS

PLAN APPROVAL  
DESIGN FLOW  
PIPING DETAILS  
SERVICE CONNECTIONS  
CONSTRUCTION  
PROTECTION OF WATER SUPPLIES  
MISCELLANEOUS REQUIREMENTS  
TESTING

SEWER MAINS

PART I - GENERAL

Related Work Specified Elsewhere  
Description  
Certificate of Compliance  
Reference Standards

PART II - PRODUCTS

Pipe Materials  
PVC  
Ductile Iron  
Clay Pipe  
Manhole Materials  
Base, Risers, Cones, and Tops  
Frame and Cover  
Manhole Steps  
Non-Shrink Grout  
Plastic Gasket Joints

PART III - EXECUTION

- Preparation
- Underground Obstruction
- Handling, and Storage
- Installation
- Laying Sewer Pipe
- Pipe Jointing
- Wyes and Risers
- Service Installations
- Manhole Construction
  - Base Construction
  - Inverts
  - Assembly of Precast Manholes
  - Drop Manholes
  - Frame and Cover Finish
- Underdrains
- Lift Station and Force Mains
- Inverted Siphons
- Leakage Testing
  - Infiltration Test
  - Exfiltration Test
  - Air Test
    - Responsibility
    - Safety
    - Equipment
    - Line Preparation
    - Test Procedures
  - Manhole Testing
- Inspection Cleaning and Lamping
- Restoration and Cleanup

Table - Allowable Pressure Drop

MINIMUM STANDARDS - CURB, GUTTER, SIDEWALKS, AND STREETS

GENERAL

PLAN APPROVAL

STREET CONSTRUCTION

- Street Layout
- Service Line Installation
- Drainage
- Monumentation

CURB, GUTTER AND SIDEWALK

- 1.00 SCOPE
- 2.00 GENERAL PROVISIONS
- 3.00 PROTECTION OF EXISTING FACILITIES
  - 3.01 General
  - 3.02 Responsibility for Repair
- 4.00 MATERIALS

- 4.01 Select Materials
- 4.02 Concrete
- 4.03 Cement
- 4.04 Aggregate
- 4.05 Wire Reinforcement
- 4.06 Air Entrainment Agents
- 4.07 Curing Compounds
- 4.08 Expansion Joint Material
- 4.09 Water
- 5.00 GRADING
  - 5.01 Compaction
- 6.00 FORMS
- 7.00 MIXING CONCRETE
  - 7.01 Job Mixed Concrete
  - 7.02 Ready Mixed Concrete
  - 7.03 Retempering Concrete
- 8.00 CONSISTENCY
- 9.00 PLACING CONCRETE
  - 9.01 General
  - 9.02 Cold Weather Concreting
  - 9.03 Hot Weather Concreting
  - 9.04 Finishing Concrete
  - 9.05 Joints
- 10.0 CURING
  - 10.01 Liquid Membrane Curing
- 11.0 DEFACING, DEFECTIVE, AND DAMAGED CONCRETE
- 12.0 BACKFILLING
- 13.0 OPENING TO TRAFFIC
- 14.0 CONNECTIONS TO EXISTING SIDEWALKS
- 15.0 REPAIRS
- 16.0 ACCEPTANCE BY TOWN

STREET DESIGN AND CONSTRUCTION

PART I - GENERAL

- Scope
- Related Work Specified Elsewhere
- Plan Submission and Approval
- Quality Assurance
  - Qualification of Asphalt Concrete Producer
  - Qualification of Testing Agency
  - Design Criteria

PART II - MATERIALS

- Selected Borrow Material
- Sub-Base
  - Gradation
- Base Course
- Prime Coat
- Tack Coat
- Paving Materials
  - Aggregate

- Paving Asphalt
- PART III - EXECUTION
  - Sub-Grade Preparation
    - Field Control
    - Grading
    - Excavation
    - Embankments
    - Select Borrow Materials
  - Sub-Base Placement and Compaction
  - Base Course
  - Asphalt Paving
    - General
    - Job Conditions
      - Weather Limitations
      - Grade Control
      - Traffic Control
    - Prime Coat
    - Tack Coat
  - Plant Mixed Asphalt Surfacing
    - Job Mixing Formula
    - Mixing Plant
    - Transporting Asphalt
  - Equipment
    - Asphalt Distributor
    - Bituminous Pavers
    - Rolling Equipment
    - Hand Tools
  - Placement
    - Allowable Tolerances
      - Density
      - Thickness
      - Surface Smoothness
  - Placing the Mix
    - Continuity of Operation
    - Paver Placing
    - Hand Placing
    - Joints
  - Compacting the Mix
  - Testing
    - Density Control
    - Depth of Asphalt Control
  - Drainage
  - Cleaning and Protection
    - Cleaning
    - Protection
    - Patching
    - Adjusting Utility Grades
  - Frame and Adjustments
    - Placing Frames
  - Acceptance by the Town

POWER AND BURIED WIRES - MINIMUM REQUIREMENTS

1. GENERAL
2. DEPTH OF BURY
3. WIRE LOCATIONS
4. BEDDING
5. MARKING TAPE
6. SEPARATION FROM OTHER UTILITIES
7. LINE IN PUBLIC RIGHTS OF WAY
8. CROSSING OTHER UTILITIES

CROSSINGS

ROADWAY CROSSINGS

ARROYO AND CANAL CROSSINGS

OVERHEAD INSULATED CROSSINGS

SLOPE STABILIZATION AND REVEGETATION

PART I - GENERAL

PART II - PRODUCTS

PART III - EXECUTION

BOARDWALK

ADDENDA

3/96

TYPICAL DRAWINGS

STANDARD BEDDING DETAIL  
CARRIER PIPE DETAIL  
WATERTIGHT ENCASEMENT  
GATE VALVE DETAIL  
FIRE HYDRANT DETAIL - Paved Street  
FIRE HYDRANT DETAIL - Gravel Street  
AIR VACUUM STATION - Type 1  
AIR VACUUM STATION - Type 2  
BLOWOFF INSTALLATION  
THRUST BLOCK DETAIL  
3/4-1" WATER SERVICE  
LARGE WATER SERVICE  
SERVICE RECONNECTION  
MANHOLE TYPICAL  
DROP MANHOLE (2 pages)  
CLEANOUT DETAIL  
RESIDENTIAL SEWER SERVICE  
STORM DRAIN INLET  
STREET DIMENSIONS  
TYPICAL PAVED STREET  
TYPICAL ROAD SECTION  
TYPICAL GRAVEL STREET  
CUL DE SAC  
CURB, CUTTER, SIDEWALK DETAILS  
VALLEY PAN DETAILS  
INTERSECTION DETAILS  
PAVEMENT REMOVAL  
DRIVEWAY DETAILS  
MONUMENT DETAILS  
HANDICAP RAMP (2 pages)  
PARKING LAYOUT  
CROSSING DETAILS